



Stonework	Rainwater Goods	Leadwork
<p>Repainting. C40 310 + 311 Repoint in this area with lime mix / Reface stones indicated as necessary</p> <p>Reface Stone. C41 110 Reface stone with 125mm reclaimed hurdwick and repoint locally around stone</p> <p>Mullions. Repoint window mullions where noted</p> <p>Loose Stone Faces. C41 110 Lightly brush down all loose stone faces until stable</p> <p>Cleaning. C40 352 Steam clean to remove heavy stains / repoint with lime mix where necessary</p>	<p>Refurbish. R10 110 Retain and refurbish cast iron rainwater goods / repaint to match railings</p> <p>Replace. R10 375 Replace rainwater goods with new cast iron painted to match railings</p> <p>Remove. R10 110 Remove section of rainwater / soil pipe no longer required</p>	<p>Cornice. H71 420 Cap cornice in lead sheet dressed with wetted drip</p> <p>Window Head. H71 420 Replace existing lead capping with new with overhand to discharge water</p> <p>Metal work</p> <p>Redecorate. M60 120 Metalwork redecorated to match railings</p>

tavistock guildhall **guildhall square west elevation fabric repairs**

<p>general</p> <ul style="list-style-type: none"> all drawings are copyright do not scale drawing report all discrepancies to project administrator all dimensions to be checked on site 	<p>key</p>	<p>notes</p> <p>Stage 4 - Tender</p> <p>Note:</p> <ul style="list-style-type: none"> Alterations and upgrades to windows and doors detailed on window schedules and window strategy elevations (GA230 - GA234) Roof works detailed on Fabric Repair Roof Plan - GA216. 	<p>rev</p> <p>T1: 08.02.19 - NBS Specification References Added to Notation</p>	<p>project: Tavistock Guildhall and Police Station</p> <p>date: Dec 2018</p> <p>scale: 1:50 @ A1 1:100 @ A3</p> <p>drawing title: Fabric Repair - Guildhall Sq. Elev.</p> <p>job no: 1041</p> <p>drawing no: GA-220</p> <p>rev: T1</p> <p>gillespie yunnie architects</p>
---	-------------------	---	--	---