



- Legend:**
- PIR SENSOR
 - DAYLIGHT DIMMING LINKED LUMINAIRE
 - ONE WAY LIGHT SWITCH
 - TWO WAY LIGHT SWITCH
 - EMERGENCY LIGHTING KEY SWITCH
 - RETRACTABLE SWITCH
 - WIRING ARRANGEMENT
 - AUDIOVISUAL CONTROL PANEL

- Notes:**
1. DO NOT SCALE THIS DRAWING. ALL DIMENSIONS IN MILLIMETRES UNLESS OTHERWISE STATED.
 2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S STRUCTURAL ENGINEERS AND M&E DRAWINGS AND THE M&E SPECIFICATION, SAMPLES SHEET AND ROOM DATA SHEETS.
 3. ALL ITEMS OF EQUIPMENT SHALL BE INSTALLED AS TO THE MANUFACTURER'S RECOMMENDATIONS.
 4. ALL INFORMATION AND LAYOUTS DETAILED ON THIS DRAWING ARE SUBJECT TO SITE DIMENSION CHECKS.
 5. KEY SWITCHES TO BE PROVIDED ON LIGHTING SWITCH PLATE WITHIN ROOM.
 6. ELECTRICAL SUB-CONTRACTOR TO SITE MEASURE ALL INFILL PANELS.
 7. THE EMERGENCY LIGHTING SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH BS5266 PART 1.
 8. SIGNAGE TO SHALL BE TO ISO:7010
 9. ALL WIRING SHALL BE CONCEALED VIA CAST IN CONDUIT. THIS REQUIRES DETAILED COORDINATION WHICH SHALL BE UNDERTAKEN BY THE ELECTRICAL SUB-CONTRACTOR.
 10. WHERE RETRACTABLE SWITCHES ARE SHOWN, OPERATION SHALL BE AS FOLLOWS: PRESS TO ENABLE, PRESS TO DISABLE, PRESS AND HOLD TO DIM UP/DOWN.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION	
FOR DETAILS OF SITE-WIDE AND GENERAL RISKS, TO BE READ IN CONJUNCTION WITH THESE NOTES, SEE THE CONTRACT DOCUMENTS AND, WHERE WORKS ARE NOTIFIABLE, THE PRE-CONSTRUCTION INFORMATION PACK ISSUED BY THE CDM CO-ORDINATOR	
IN ADDITION TO THE RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING RISKS AND INFORMATION:	
DISMANTLING / DEMOLITION (Future)	
Di.	
Dii.	
Diii.	
Div.	
IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT	

LUMINAIRE SCHEDULE

REFERENCE	OUTPUT(W)	MAKE AND MANUFACTURER	IMAGE	REFERENCE	OUTPUT(W)	MAKE AND MANUFACTURER	IMAGE
L1	41	WHITECROFT AVENUE METRO SUSPENDED 1.25m 4350lm SILVER 300K OVAL DIFFUSER		L10	-	OMITTED	
L2	25	WHITECROFT MIRAGE LED 3000lm 4000K		L11	12	WHITECROFT ACCENT	
L3	17	WHITECROFT HORIZON 360 1700lm 4000K		L12E	3	WHITECROFT FLORIN E3 SURFACE MOUNTED	
L4	12	WHITECROFT STARLINE FLEX		L13	-	REPLICA GAS WALL LIGHT	
L5	21	WHITECROFT MINION		L14	3.8	WHITECROFT MARINE LF LED 300Lm 25° BEAM	
L6	35	SOVEREIGN GLOBE		L15	30	WHITECROFT MINI SPT WIDEBEAM C/W COWL, SHUTTER AND FILTER PACK, 2140lm	
L7	-	OMITTED		L16	10	WHITECROFT MIRAGE LED SURFACE WHITE 200mm BODY, 1100Lm	
L8	13.6	IGUZZINI IANDER WALL MOUNTED 1120lm AK55 IP66 RATED c/w REMOTE EMERGENCY BATTERY PACK MOUNTED AT 2.5m ABOVE FINISH FLOOR LEVEL		L17	45	WHITECROFT SPECTRE WALL ? DIMMABLE COMMISSIONED TO 5090 LIGHT OUTPUT	
L9	19	WHITECROFT STYLUS		EXIT	4.5	WHITECROFT CONCERT EXIS STANDALONE DIRECTIONAL ILLUMINATED EXIT SIGN	

Rev	Date	By	Chk	Aprvd	Description
T02	03.04.19	OJR	TXK	NJS	L4 ADDED
T01	07.03.19	EIL	TXK	NJS	MINOR AMENDMENTS MADE

PROJECT
Tavistock Guildhall

CLIENT
Tavistock Guildhall

www.methodllp.com Swindon Tel: 01793 822044

DRAWING TITLE
Proposed Lighting Layout
First Floor

SUITABILITY
D2 - FOR TENDER

DATE	SCALE	DRAWN BY	CHEK BY	APVD BY
26.01.17	1:50 - A1	BJP	NJS	NJS

DRAWING NUMBER	REVISION NO.
716LGH-MET-00-01-DR-E-Ss_70_80-0001	D2 - T02

Scaling Note: Do NOT scale from this drawing.